




Oyster Prisms



- 131 Oyster prisms constructed from jute fiber and concrete
- Prisms will be filled with oyster shell
- Prisms are 4ft x 14in x 12in

Oyster Gabions



- 832 Oyster gabions constructed from wire
- Gabions will be filled with oyster shell
- Gabions are 1ft x 1ft x 2ft

Mangrove Planter Boxes



- 27 wooden mangrove planter boxes will be constructed
- Boxes will be filled with coquina rock and sand
- Planter boxes will be 4ft x 2.5ft x 3ft
- 80 mangroves will be planted in the boxes

Floating Oyster Habitat and Mangrove Planter



- 20 floating concrete elements
- Each element will support 16 sqft of seeded oyster and 1 mangrove
- Elements are 3ft x 2ft with a 2ft fin in the water

**McNabb Park
Living Shoreline**

